

DIVISION _____

Specification Section # _____

**BIO/CR-6
Hygienic Ceiling Panel**

PART 1 GENERAL

Furnish and install the Bio/CR-6 Hygienic Ceiling Panel designed for healthcare applications as described in this Section. Drawings and General Provisions of Contract, including General and Supplementary Conditions and Division 1 Specifications apply to work in this section.

1.1 RELATED WORK: (NOTE TO SPECIFIER: Include appropriate detail drawings and information pertinent to the specific project.)

1.2 SUBMITTALS

- 1.2.1 Submit # _____ samples of the materials to be used to show corner and joining details as well as final panel finish.
- 1.2.2 All parties wishing to have materials considered as equals for this project must submit such materials for evaluation to the design professional at least 10 (ten) days prior to bid date. Bidders not complying with this requirement will be considered non-responsive.

1.3 QUALITY ASSURANCE

- 1.3.1 Provide Single Source responsibility for the supply of all ceiling finish materials used in the installation.
- 1.3.2 A Contractor approved by Manufacturer must perform installation.

1.4 DELIVERY, HANDLING AND STORAGE

- 1.4.1 Deliver materials packaged so that materials are clearly marked and identifiable showing the following:
 - A) Product Name
 - B) Manufacturer's Name
 - C) Component Designation
- 1.4.2 Handle Materials by methods to prevent damage
- 1.4.3 Inspect direct job-site deliveries to assure that quantities are correct and that materials comply with specifications and are not damaged.
- 1.4.4 Replace, at no cost to owners, materials that are found defective either in manufacture, handling or storage.
- 1.4.5 Store materials on site at the final installation temperature for at least 24 hours prior to, during, and after installation.

1.5 WARRANTY

- 1.5.1 Provide a limited 10 year warranty for materials and installation against any defects in manufacturing and workmanship.

Life Science Products, Inc. Technical Specification
Bio/CR-6 Hygienic Ceiling Panel

1.6 JOB CONDITIONS

- 1.6.1 A Representative of the Manufacturer shall visit the job-site with the Contractor prior to installation to insure that field conditions including but not limited to hacked blocks are corrected or are acceptable for installation.
- 1.6.2 For 24 hours before, during the installation, and for 72 hours after the installation, maintain temperature and relative humidity at in-service conditions.

PART 2 PRODUCTS

For the purposes of this specification, Bio/CR-6 Hygienic Ceiling System by Life Science Products, Inc. (800-638-9874) is used as the standard.

2.1 MATERIALS

- 2.1.1 System Overview: The ceiling system as specified shall consist of composite ceiling panels manufactured from materials having physical properties as specified in Section 2.1.3 below. Panels shall have a consistent extra smooth semi-gloss finish with 100% solids urethane seam sealant.
- 2.1.2 Panels: The panels used in this system shall be Bio/CR-6 composite ceiling panel and shall be 3 mm thick. The face of panels shall be extra smooth (no fabric print through). The panel surface finish shall be semi-glossy and the panel must be ASTM E 84 Class A for smoke and flame spread. The panel will be supplied in standard 48" wide and available is 8', 9' and 10' height. The vertical edge shall be square edge design. The panel vertical seam shall be sealed with a 100% solids urethane sealant to match the surface of the panel.
- 2.1.3 The panels shall have the following properties:

Finish:

Fire Rating: **Class 1 ASTM E 84 for flame spread of 25 or less**

Light Reflectance: **LR-1, 0.75 or greater**

Maximum Weight: **1.0 lbs. per square foot**

Finish: **Polyester gel coat**

Standard Sizes: **4' X 8', 4' X 9' and 4' x 10'**

Panel thickness: **3 mm**

Color: **White**

Finish: **Semi-Gloss**

PART 3 EXECUTION

- 3.0.1 Apply adhesive of type recommended by Manufacturer to the entire back side of the panel, all the way to the edges. Follow Manufacturers recommendations for application and "open times" of the adhesive.
- 3.0.3 Panels are designed to be mounted directly onto the substrate. Put the panels in place against the substrate approximately ½ inch above the floor. Press and roll the panel against the substrate to assure proper contact between the panel and the substrate.
- 3.0.4 If necessary, apply pressure to the center of the panel using a weighted lever until adhesive cures.
- 3.0.5 Fill the exposed seam with urethane sealant and strike flush. Follow Manufacturer's instructions for taping and masking adjacent panel face.